


Public Information Meeting

October 9, 2019


State Project No. 0086-0092
Replacement of Bridge No. 05417
Route 109 over Nylbs Brook
Morris, CT



Connecticut Department of Transportation



Location of Project



Location of Project



**Route 109 (Eastbound
towards John Weik Road)**



**Route 109 (Westbound
towards Cavalry Hill Road)**

CTDOT Role and Mission

Responsible for **engineering design, construction and inspection** of transportation projects.

Our mission is to allocate State/Federal bridge program **funds** to address identified **structural deficiencies** on eligible bridges.



Project Goals

- Address **poor condition** of Bridge No. 05417
- Minimize disturbance to traveling public
- Complete construction in a timely manner
- Effectively use funds



Existing Bridge Data

- Bridge Number **05417**
- Originally built in **1956**
- Structure type: Single span corrugated steel pipe-arch culvert with 3'-6" of fill over structure.



- Function
 - Carries Route 109 (Lakeside Road) over Nylbs Brook
 - Estimated **Average Daily Traffic** (ADT, 2015) is **2,100** vehicles (**3%** trucks)
- Dimensions
 - Opening: Width = **11'-10"** Height = **7'-7"**
 - Culvert Length = **62'-4"**

Existing Conditions

- Large perforations in metal culvert leading to loss of fill.
- Significant pitting and deterioration along waterline throughout the structure.



Existing Site Conditions



Inlet

Existing Site Conditions




Outlet

Proposed Project No. 0086-0092

Replacement of Bridge No. 05417



Existing Structure:



Proposed Structure:

Reason:

- Poor condition of superstructure (rating = 4): Deterioration and pitting throughout length of metal culvert. Large perforations and loss of fill found along waterline.
- Replacement structure type meets all of the site constraints

Scope:

- Replace the existing bridge with a precast, 4-sided 10' x 8' box culvert buried 1.5' in natural streambed material.

Replacement of 24" HDPE Pipe

- 24" HDPE approximately 425 feet to the East near the location of the transfer station.
- Hydraulically inadequate:
 - overtops the roadway at any storm close to or exceeding the 1-year storm event.
- Replace with a 5'-0" x 2'-0" precast concrete box culvert




Selected Structure Benefits



- ***Meets DEEP Fisheries recommendations:***
 - *Invert elevations set 1.5 ft lower than existing to provide 1.5 ft of natural streambed material within culvert while keeping the streambed elevations at inverts matching existing.*
- ***Designed for 100-yr flood frequency to be conveyed while maintaining greater than one foot of freeboard from the edge of Route 109***
- ***Addresses any potential scour concerns without need for a deep foundation***
- ***Limits duration of temporary watercourse impact to no more than 2 weeks***
- ***Allows accelerated construction (ABC) resulting in a short construction duration (1 season total, 14 day road closure) that falls within the DEEP Fisheries unconfined instream work restrictions***
- **Anticipated permits: ACOE PCN, IWRD General, FMC, CT-GP Addendum**




Structural Plan



Structural Plan




Accelerated Bridge Construction




Benefits of Accelerated Bridge Construction (ABC)

- **Minimize traffic impacts**
- **Improve work-zone safety**
- **Reduce total project delivery time**
- **Reduce project costs incurred by temporary structures, remote site locations and limited construction periods**
- **Improve site constructability**
- **Reduce environmental impacts**




Proposed Detour Plan

- Preliminary analysis deemed closure/detour feasible.
- Adds approximately 6.5 miles to through traffic.
- Proposed detour route is the same that was used for the construction of Project 150-131, bridge No. 06786.



Preliminary Rights of Way Impacts



ROW - Relevant Law

- **State of Connecticut**

C.G.S. Sections 13a-73 & 13a-98e


- **Federal**

Uniform Relocation Assistance and Real Properties Acquisition Policies Act of 1970, as amended.



ROW - Acquisition Process

- Letter of Intent to Acquire
- Valuation
- Offer of Just Compensation
- Negotiation
- Acquisition
 - Agreement
 - Eminent Domain/Condemnation
 - » 6 month appeal period



Project Schedule & Cost

Schedule:

- Construction is anticipated to start in April 2022

Cost:


- Approximately \$1,200,000

Duration:

- Overall: Approximately 5 months

Construction Method:

- Accelerated Bridge Construction (ABC)
- Road closure: 14 consecutive days in Late July/Early August of 2022



***THANK YOU FOR YOUR
TIME AND ATTENTION!!***

Q & A

Connecticut Department of Transportation



For Additional Information

- To access this presentation via the internet, please go to: "Calendar of DOT Events" on the Connecticut DOT website (www.ct.gov/dot)

- **Contact us:**

Connecticut Department of Transportation
2800 Berlin Turnpike, Newington, CT 06111

- ***Principal Engineer:*** Mary E. Baker
Email: Mary.Baker@ct.gov | **Phone:** 860 - 594 - 3402
- ***Project Manager:*** Bao K. Chuong
Email: Bao.Chuong@ct.gov | **Phone:** 860 - 594 - 3316
- ***Project Engineer:*** Zoltan M. Kanyo
Email: Zoltan.Kanyo@ct.gov | **Phone:** 860 - 594 - 3166
- ***Design Engineer:*** Nicholas W. McNulty
Email: Nicholas.McNulty@ct.gov | **Phone:** 860 - 594 - 3254

